

Ref	Description	Quantity	Units	Rate	Value
	M50 RUBBER / PLASTIC / CORK / LINO / CARPET TILING / SHEETING				-
					-
1	Carpet Flooring; Identified As CPT-1; Manufacture - Forbo; Product reference - Desso ; 500mm x 500mm x 5.7mm Carpet Tiles; Colour - 357 Mild Grey Or Similar Approved; Laid In Accordance With Manufacturers Recommendations				-
					-
1.2	Floors				-
					-
	level and to falls only less than or equal to 15° from horizontal	1670	m2	£ 13.28	£ 22,177.60
					£ -
2	Vinyl Flooring; Identified As VL-1; Manufacturer - Polyflor; Product reference - S-201; Static Dissipative Adhesive And Copper Grounding Strips; Polish Floor; Colour - Frosted Glass; Laid In Accordance With Manufacturers Recommendations				£ -
					£ -
2.1	Floors				£ -
					£ -
	level and to falls only less than or equal to 15° from horizontal	39	m2	£ 35.20	£ 1,372.80
					£ -
3	Vinyl Flooring; Identified As VL-2; Manufacturer - Polyflor; Product reference - XL PU; 2mm Vinyl Sheet Flooring; Colour - Fossil; Laid In Accordance With Manufacturers Recommendations				£ -
					£ -
3.1	Floors				£ -
					£ -
	level and to falls only less than or equal to 15° from horizontal	245	m2	£ 19.98	£ 4,895.10
					£ -
					£ -
4	Vinyl Based Skirting; Manufacturer - as contractors proposals; Product reference - as contractors proposals; Allowance For; Vinyl Based Skirting Detail; Colour - Mild Grey; Applied in Accordance With Manufacturers Recommendations; Full Details - TBC				£ -
					£ -
4.1	Floors				£ -
					£ -
	isolated surfaces; girth less than or equal to 300mm	3220	m	£ 6.28	£ 20,221.60

						£	-
	<u>N10 GENERAL FIXTURES / FURNITURE / EQUIPMENT</u>					£	-
						£	-
5	Entrance Barrier Matting; Identified As CPT-2; Manufacturer - Gradus; Product reference - Esplanade 8500; Primary Entrance Barrier Matting Within 25mm Recess; 18mm Closed Construction With Double Wipers; Black Standard Rubber Wipers And Aluminium Strip; Or Similar Approved; Installed In Accordance With Manufacturers Recommendations					£	-
						£	-
5.1	Barrier Matting 12mm Gradus	72	m2	£	331.00	£	23,832.00
5.2	Frame	48	m	£	14.70	£	705.60
						£	-
6	<u>Extra Cost Items</u>					£	-
						£	-
6.1	DPM to all Vinyl Areas	287	m2	£	8.10	£	2,324.70
6.2	Single coat latex up to 3mm thick to all Vinyl Areas	278	m2	£	7.69	£	2,137.82
6.3	Dust Sealer to Vinyl Areas above	1	item		included		included
6.4	Cutting in floor boxes	77	nr	£	6.97	£	536.69
6.5	6mm plywood floor prep	0	m2	£	13.69		Rate Only
6.6	Threshold Strips	1	item	£	400.00		Rate Only
7	<u>Prelims and Attendances</u>						
7.1	Working Supervisor	1	item		included		-
7.2	Vertical Distribution	1	item		included		-
7.3	Horizontal Distribution	1	item		included		-
8	<u>Dayworks</u>						
8.1	Skilled person	1	item	£	30.00		Rate Only
8.2	Unskilled person	1	item	£	20.00		Rate Only
8.3	Return Visit Charge - 1 days works (Approx 100m2 required for 1 day)	1	day	£	400.00		Rate Only
9	MCD				4.00%	-£	3,128.16
	Total Scope Cost						£ 75,075.75